



NOT TO SCALE



12" TRENCH DRAIN DETAIL



DRAIN MANHOLE (DMH) WITH TRAP

1. PROVIDE "V" KNOCKOUTS FOR PIPES WITH 2" MAX. CLEARANCE TO OUTSIDE OF PIPE. MORTAR ALL PIPE CONNECTIONS. 2. JOINT SEALANT BETWEEN PRECAST

BUTYL RUBBER. 3. DRAIN MANHOLE FRAME AND GRATE SHALL BE SET IN FULL MORTAR BED. ADJUST TO GRADE WITH CLAY BRICK AND MORTAR (2 BRICK COURSES TYPICALLY, 5 BRICK COURSES MAXIMUM.

SECTIONS SHALL BE PREFORMED


4. HOOD SHALL BE "THE ELIMINATOR" OIL & FLOATING DEBRIS TRAP AS MANUFACTURED BY GROUND WATER RESCUE, INC., QUINCY, MA., TEL. 617-773-1128 ON THE WEB @ WWW.KLEANSTREAM.COM


SMITH No. 45084

SITE DETAILS LOTS 1 & 2 123 WESTFIELD ST. DEDHAM, MASSACHUSETTS FEBRUARY 5, 2020 SCALE: NTS



Norwood Engineering Company, Inc. Consulting Engineers, Land Surveyors 1410 ROUTE ONE, NORWOOD, MA 02062 TEL. (781)762-0143 FAX (781)762-8595






SCS SOIL TYPE IS CLASSIFIED AS HOLLIS-ROCK OUTCROP-CHARLTON COMPLEX.

NOTE: TEST HOLES TP-25, TP-26, TP-27 & TP-28 WERE WITNESSED BY LUCAS KLIM, SOIL EVALUATOR, AND CATHERINE CARDINALE FOR THE TOWN OF DEDHAM BOARD OF HEALTH, ON JULY 5, 2018.

PERCOLATION TEST RESULTS

TP-25	TP-27
DATE: 7-5-18	DATE: 7-5-18
PRESOAK: 12:57	PRESOAK: 1: 15
END PRESOAK: 1:12	END PRESOAK: 1: 3
TIME @ 12": 1:13	TIME @ 12": 1:30
TIME @ 9": 1:42	TIME @ 9": 2:03
TIME @ 6": 2:21	TIME @ 6": 2:51
TIME(9"-6"): 39 MIN	TIME(9"-6"): 48 M
RATE: 13 MPI	RATE: 16 MPI




NOTES:

 2 3/8 IN. (60 MM) THICK PAVERS MAY BE USED IN PEDESTRIAN AND RESIDENTIAL APPLICATIONS.
 1 1/2" TO 2" CRUSHED STONE SUBBASE THICKNESS VARIES WITH DESIGN. CONSULT ICPI PERMEABLE INTERLOCKING CONCRETE PAVEMENT MANUAL.

PERMEABLE PAVEMENT WITH FULL EXFILTRATION TO SOIL SUBGRADE

SOIL LOGS



DEDHAM BOARD OF HEALTH, ON NOVEMBER 21, 2017 & JULY 5, 2018.

PERCOLATION TEST RESULTS

TP-21

DATE: 7-5-18

PRESOAK: 12: 27 PM

25 GALLONS

DURING

PRE-SOAK

RATE: < 2 MPI

TP-23

DATE: 7-5-18

PRESOAK: 12: 27 PM

END PRESOAK: 12: 42

TIME @ 12": 12:42

TIME @ 9": 12:55

TIME @ 6": 1:08

TIME(9"-6"): 13 MIN

RATE: 5 MPI

INSTALL SPLIT FLOW DIVERTER TO PREVENT~

DRAIN SPOUT BACKUP

SPLASH BLOCK -

4" PVC CAP / FOR CLEANOUT

- FOUNDATION

4" PVC WYE -

3/4"- 1 1/2"

4" PVC DRAIN PIPE

SET AT S=0.01 MIN

WASHED STONE

DOWNSPOUT DETAIL w/ DIVERTER

NOT TO SCALE

TP-1

DATE: 11-21-17


PRESOAK: 1:31 PM

25 GALLONS

DURING

PRE-SOAK

RATE: < 2 MPI



SO'-O" MIN.

FILTER
FABRIC
PROFILE
SO'-O" MIN.

FILTER
FABRIC
PROFILE
SO'-O" MIN.

PLAN VIEW

FILTER
FABRIC
PROFILE
SO'-O" MIN.

FILTER
FABRIC
PROFILE
SO'-O" MIN.

PLAN VIEW

FILTER
FABRIC
PAVEMENT

O

PAVEMENT

O


PAVEMENT

5 MPI

 STONE SIZE - USE 2" STONE, OR RECLAIMED OR RECYCLED CONCRETE EQUIVALENT.


- 2. LENGTH AS REQUIRED, BUT NOT LESS THAN 50 FEET (EXCEPT ON A SINGLE RESIDENCE LOT WHERE A 30 FOOT MINIMUM LENGTH WOULD APPLY).
- 3. THICKNESS NOT LESS THAN SIX (6) INCHES.
- 4. WIDTH TEN (10) FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCURS.
- 5: FILTER FABRIC WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE. FILTER WILL NOT BE REQUIRED ON A SINGLE FAMILY RESIDENCE
- 6. SURFACE WATER ALL SURFACE WATER FLOWING OR DIVERTED TOWARD, CONSTRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE. IF PIPE IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES WILL BE PERMITTED.
- 7. MAINTENANCE THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS—OF—WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHT—OF—WAY MUST BE REMOVED IMMEDIATELY.
- B. WASHING WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHTS—OF —WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.
- 9. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN EVENT.

STABILIZED CONSTRUCTION ENTRANCE



TREE PROTECTION DETAIL

SCALE: NTS



NOT TO SCALE

1. PRIOR TO ANY CONSTRUCTION, IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT DIG SAFE AT 1-888-344-7233 AT LEAST 72 HOURS PRIOR TO ANY CONSTRUCTION.

CONSTRUCTION NOTES

- 2. PRIOR TO ANY WORK IN PUBLIC WAYS THE CONTRACTOR
 SHALL OBTAIN A STREET OPENING PERMIT FROM THE TOWN OF
- 3. THE TOWN OF DEDHAM SHALL BE NOTIFIED 48 HOURS IN ADVANCE OF ANY CONSTRUCTION WITHIN A PUBLIC WAY.
- 4. ALL CONSTRUCTION SHALL CONFORM TO THE LATEST VERSION OF THE TOWN OF DEDHAM DESIGN AND CONSTRUCTION STANDARDS AS APPLICABLE.
- 5. ALL WATER SERVICE LINE TESTING OR CONSTRUCTION SHALL BE COORDINATED WITH DEDHAM—WESTWOOD WATER COMPANY. CONSTRUCTION MATERIALS, METHODS AND TESTING SHALL MEET THEIR SPECIFICATIONS.
- 6. THE DEDHAM—WESTWOOD WATER COMPANY SHALL BE NOTIFIED 48 HOURS IN ADVANCE OF ANY CONSTRUCTION RELATED TO THEIR WATER SYSTEM.
- 7. THE DEDHAM DEPARTMENT OF PUBLIC WORKS SHALL BE NOTIFIED 48 HOURS IN ADVANCE OF ANY CONSTRUCTION ASSOCIATED WITH THE TOWN'S SEWER OR DRAIN SYSTEMS.
- 8. THE LOT SHOWN HEREON IS IN ZONE X, AN AREA DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOOD PLAIN, AS SHOWN ON THE HUD FLOOD INSURANCE RATE MAP DATED JULY 17, 2012, MAP 25021C0039E.
- 9. ALL LAWN AREAS TO BE LOAMED (4") AND SEEDED.
- 10. THE CONSERVATION COMMISSION SHALL BE NOTIFIED PRIOR TO THE START OF ANY WORK IN ACCORDANCE WITH THE PROJECT PERMITS.
- CONSTRUCTION SEQUENCE FOR STORMWATER MANAGEMENT
 AND SEDIMENTATION CONTROL

PRE-CONSTRUCTION MEETING:

A. * THE CONTRACTOR SHALL ATTEND A PRE—CONSTRUCTION
MEETING HELD BY THE APPLICANT. IT SHALL BE A MEETING
WITH THE CONSTRUCTION SUPERINTENDENT, HIS ENGINEER,
AND THE TOWN'S CONSERVATION AGENT. THE PURPOSE OF
THE MEETING WILL BE TO REVIEW THE PROJECT STORMWATER
PERMIT AND OUTLINE THE PERFORMANCE STANDARDS THAT WILL
BE REQUIRED TO TO FULFILL THE REQUIREMENTS IN THE PERMIT.

SEDIMENT AND EROSION CONTROL:

- B. * INSTALL COMPOST SOCK AND CONSTRUCTION FENCE.
- * PERFORM SITE CONSTUCTION.
- * SWEEP WESTFIELD STREET DAILY TO REMOVE SEDIMENT
- * WATER DISTURBED AREAS AS NEEDED TO PREVENT
- DUST AND WIND BLOWN EROSION

 * LOAM AND SEED ALL DISTURBED AREAS. WATER AS NECESSARY.
- * CLEAN OUT DRAINAGE STRUCTURES AND REMOVE SILTSACKS, COMPOST SOCK/CONSTRUCTION FENCE AFTER INSPECTION BY THE CONSERVATION COMMISSION AND DISTURBED AREAS ARE FULLY STABILIZED.

DEWATERING MEASURES:


C. * DEWATERING MAY BE NEEDED DURING CONSTRUCTION. IF DEWATERING IS NECESSARY THE DISCHARGE SHALL BE TO A COMPOST SOCK/CRUSHED STONE FILTER.


SITE DETAILS LOTS 1 &2 123 WESTFIELD ST. DEDHAM, MASSACHUSETTS


SCALE: NTS FEBRUARY 5, 2020

Norwood Engineering

Norwood Engineering Company, Inc. Consulting Engineers, Land Surveyors 1410 ROUTE ONE, NORWOOD, MA 02062 TEL. (781)762-0143 FAX (781)762-8595







THIS STANDARD HAS BEEN MET.

OUTLET PIPES (3)

PLAN

(TYP)

6" CRUSHED STONE BASE

ON NATIVE SOIL OR

IN FILL. LEVEL BASE


COMPACTED GRAVEL IF

SECTION

DISTRIBUTION BOX

WIGGIN MEANS PRECAST DB-3 H-20 (DB3H) OR EQUAL

NOT TO SCALE



-INSPECTION PORTS

TRENCH CONFIGURATION OF

7-4.83'X8.5' CHAMBERS WITH 2.0' OF STONE SIDES AND ENDS

SEE DETAIL

11' 4" SCH 40 PVC SEWER @ S=0.020

→47' 4" SCH 40 PVC

1500 GALLON (2) COMPARTMENT

SEPTIC TANK - RIMS TO GRADE

- FINISHED GRADE: 162.2±-161.9±

-FINISHED GRADE: 162.0 ±

17' 4" SCH 40 PVC

DISTRIBUTION PIPING TO HAVE TIGHT JOINTS

SYSTEM PROFILE

© S=0.005

___ D BOX W/ 3 OUTLETS

DESIGN CALCULATIONS :

FLOW: SINGLE FAMILY DWELLING WITH 4 BDRMS @ 110 GPD/BDRM = 440 GPD NO GARBAGE GRINDER

SEPTIC TANK

FINISHED GRADE: 161.2±-162.1±

1 36" MAX.

BOTTOM HOLE (NO MOTTLES) @ 151.9 @ TP-27

157.0

3:1 MAX.

- 2% MINIMUM SLOPE OVER

LEACHING AREA

TOTAL DESIGN FLOW: 440 GPD

SEPTIC TANK SIZE: 1500 GALLONS (2 COMPARTMENT TANK)(MINIMUM) 440 GPD X 2 (1ST COMPARTMENT) + 440 GPD (SECOND) = 1320 GPD

SOIL ABSORPTION SYSTEM

PERC RATE: 16 MPI-CL II SOILS (USE 20 MPI)

DESIGN FLOW REQUIRED: = 440 GPD

LEACHING REQUIRED: 440 GPD/0.53 GPD/SF = 831.0 SF LEACHING PROVIDED: CHAMBER TRENCH WITH STONE

BOTTOM AREA: 8.83'X63.5' = 560.0 SF

SIDE AREA: 63.5'X2'X2 = 254.0 SFEND AREA: 8.83'X2'X2 = 35.0 SF

= 849.0 SF > 831.0 SF TOTAL AREA:

(1500 GALLON MINIMUM)

GENERAL NOTES

INSPECTION NOTES - SEPTIC SYSTEM

- 1) COMPONENTS ARE NOT TO BE BACKFILLED WITHOUT INSPECTION AND PERMISSION BY THE BOARD OF HEALTH.
- 2) A DESIGNER'S AS BUILT DRAWING AND CERTIFICATION OF CONSTRUCTION IS REQUIRED IN ADDITION TO A LOCATION INSPECTION BY THE DESIGNER.

THE INSTALLER TO COORDINATE PROJECT ACCORDINGLY.

- 3) THE SYSTEM INSTALLER SHALL CERTIFY CONSTRUCTION OF THE SYSTEM.
- 4) THE SYSTEM AREA SHALL BE STAKED AND FLAGGED OR OTHERWISE BARRICADED FROM DATE OF INSTALLATION TO DATE CERTIFICATE OF COMPLIANCE IS ISSUED.

SEPTIC SYSTEM FILL SPECIFICATION (FROM 310 CMR 15.255(3)

FILL MATERIAL FOR SYSTEMS CONSTRUCTED IN FILL SHALL CONSIST OF SELECT ON-SITE OR IMPORTED SOIL MATERIAL. THE FILL SHALL BE COM-PRISED OF CLEAN, GRANULAR SAND, FREE FROM ORGANIC MATTER AND DELETER-IOUS SUBSTANCES. MIXTURES AND LAYERS OF DIFFERENT CLASSES OF SOIL SHALL NOT BE USED. THE FILL MATERIAL SHALL NOT CONTAIN ANY MATERIAL LARGER THAN TWO INCHES.

A SIEVE ANALYSIS USING A #4 SIEVE SHALL BE PERFORMED ON A REPRE-SENTATIVE SAMPLE OF THE FILL. UP TO 45% BY WEIGHT OF THE FILL SAMPLE MAY BE RETAINED ON THE #4 SIEVE. SIEVE ANALYSIS SHALL ALSO BE PERFORMED ON THE FRACTION OF THE FILL SAMPLE PASSING THE #4 SIEVE. SUCH ANALYSIS MUST DEMONSTRATE THAT THE MATERIAL MEETS EACH OF THE FOLLOWING SPECIFICATIONS. SIEVE SIZE EFFECTIVE PARTICLE SIZE % THAT MUST PASS SIEVE

100% 10%-100% 0.30 mm 0.15 mm 0%- 20% 0.075 mm 0%- 5%


- CONSTRUCTION NOTES SEPTIC SYSTEM 1) VEHICULAR TRAFFIC, PARKING OF VEHICLES, STOCKPILING OF MATERIALS AND STORAGE OF EQUIPMENT OVER LEACHING AREA PROHIBITED AT ALL
- 2) REMOVE ANY TOPSOIL, SUBSOIL OR ANY OTHER UNSUITABLE MATERIAL BELOW THE INVERT FOR A DISTANCE OF 5 FEET AROUND THE PROPOSED FACILITY. FILL MATERIAL MUST MEET THE SPECIFICATIONS OF 310 CMR 15.255(3) OF
- 3) ALL CONSTRUCTION IS TO CONFORM TO THE REQUIREMENTS OF THE MASSACHU-SETTS STATE ENVIRONMENTAL CODE, TITLE V, AND THE DEDHAM BOARD OF HEALTH REGULATIONS.
- 4) SANITARY TEES ARE TO BE INSTALLED AT BOTH THE INLET AND OUTLET OF THE SEPTIC TANK. BUILT-IN TEES ARE NOT ALLOWED.
- 5) EXCAVATION IS TO BE DRY AND SCARIFIED.
- 6) FILL SHALL BE STOCKPILED AT EDGE OF FOUNDATION AND PUSHED OR CAST INWARD OVER EXCAVATED AREA.
- 7) FILL SHALL NOT BE PLACED DURING RAIN OR SNOW STORMS.
- 8) DEWATERING IS REQUIRED IF FILL IS TO BE PLACED BELOW GROUNDWATER.
- 9) BUILDING SEWER IS TO HAVE TIGHT JOINTS & LAID ON A FIRM COMPACTED
- 10) ALL SYSTEM COMPONENTS SHALL BE MARKED WITH MAGNETIC MARKING TAPE. 11) AN INSPECTION PORT, WHICH CONSISTS OF A PERFORATED PIPE PLACED
- VERTICALLY DOWN INTO THE STONE TO THE NATURALLY OCCURRING SOIL OR SAND BELOW THE STONE, IS REQUIRED. SCREW TYPE CAP ACCESSIBLE TO WITHIN 3" OF PROPOSED GRADE.
- 12) BENCHMARK TO BE SET WITHIN 50' OF SEPTIC SYSTEM AT THE TIME OF CONSTRUCTION IN AN AREA NOT SUBJECT TO DISLOCATION.

SEPTIC SYSTEM PLAN LOT 1 DETAILS 123 WESTFIELD ST. DEDHAM, MASSACHUSETTS

FEBRUARY 5, 2020 SCALE: NTS

Norwood Engineering Company, Inc.

Consulting Engineers, Land Surveyors 1410 ROUTE ONE, NORWOOD, MA 02062 TEL. (781)762-0143 FAX (781)762-8595



10296-01

2 COMPARTMENT SEPTIC TANK

3-1/2" BASE ✓


6" CRUSHED STONE BASE

ON NATIVE SOIL OR

IN FILL. LEVEL BASE

COMPACTED GRAVEL IF

WIGGIN MEANS 1500 GALLON H20 MONOLITHIC SEPTIC TANK (TM1500H) OR EQUAL NOT TO SCALE





BOTTOM TANK ELEVATION: 155.4 ±

LEACHING CHAMBER


WIGGIN MEANS 500 GALLON H-10 LEACHING CHAMBER (LC500) OR EQUAL

NOT TO SCALE





SYSTEM PROFILE



DESIGN CALCULATIONS:

FLOW: SINGLE FAMILY DWELLING WITH 4 BDRMS @ 110 GPD/BDRM = 440 GPD NO GARBAGE GRINDER

SEPTIC TANK

TOTAL DESIGN FLOW: 440 GPD

SEPTIC TANK SIZE: 1500 GALLONS (2 COMPARTMENT TANK)(MINIMUM) 440 GPD X 2 (1ST COMPARTMENT) + 440 GPD (SECOND) = 1320 GPD

SOIL ABSORPTION SYSTEM

PERC RATE: <=5 MPI-CL I SOILS

DESIGN FLOW REQUIRED: = 440 GPD

LEACHING REQUIRED: 440 GPD/0.74 GPD/SF = 595 SF LEACHING PROVIDED: CHAMBER TRENCH WITH STONE BOTTOM AREA: 8.83'X46.5' = 410.0 SF

186.0 SF SIDE AREA: 46.5'X2'X2 = 35.0 SF END AREA: 8.83'X2'X2 = = 631.0 SF > 595 SF TOTAL AREA:

(1500 GALLON MINIMUM)

GENERAL NOTES

INSPECTION NOTES - SEPTIC SYSTEM

- 1) COMPONENTS ARE NOT TO BE BACKFILLED WITHOUT INSPECTION AND PERMISSION BY THE BOARD OF HEALTH.
- 2) A DESIGNER'S AS BUILT DRAWING AND CERTIFICATION OF CONSTRUCTION IS REQUIRED IN ADDITION TO A LOCATION INSPECTION BY THE DESIGNER.
- THE INSTALLER TO COORDINATE PROJECT ACCORDINGLY. 3) THE SYSTEM INSTALLER SHALL CERTIFY CONSTRUCTION OF THE SYSTEM.
- 4) THE SYSTEM AREA SHALL BE STAKED AND FLAGGED OR OTHERWISE
- BARRICADED FROM DATE OF INSTALLATION TO DATE CERTIFICATE OF COMPLIANCE IS ISSUED.

SEPTIC SYSTEM FILL SPECIFICATION (FROM 310 CMR 15.255(3)

FILL MATERIAL FOR SYSTEMS CONSTRUCTED IN FILL SHALL CONSIST OF SELECT ON-SITE OR IMPORTED SOIL MATERIAL. THE FILL SHALL BE COM-PRISED OF CLEAN, GRANULAR SAND, FREE FROM ORGANIC MATTER AND DELETER-IOUS SUBSTANCES. MIXTURES AND LAYERS OF DIFFERENT CLASSES OF SOIL SHALL NOT BE USED. THE FILL MATERIAL SHALL NOT CONTAIN ANY MATERIAL LARGER THAN TWO INCHES.

A SIEVE ANALYSIS USING A #4 SIEVE SHALL BE PERFORMED ON A REPRE-SENTATIVE SAMPLE OF THE FILL. UP TO 45% BY WEIGHT OF THE FILL SAMPLE MAY BE RETAINED ON THE #4 SIEVE. SIEVE ANALYSIS SHALL ALSO BE PERFORMED ON THE FRACTION OF THE FILL SAMPLE PASSING THE #4 SIEVE. SUCH ANALYSIS MUST DEMONSTRATE THAT THE MATERIAL MEETS EACH OF THE FOLLOWING SPECIFICATIONS.

SIEVE SIZE EFFECTIVE PARTICLE SIZE % THAT MUST PASS SIEVE 0.30 mm 10%-100% 0.15 mm 0%- 20% 0.075 mm 0%- 5%

- <u>CONSTRUCTION NOTES SEPTIC SYSTEM</u>


 1) VEHICULAR TRAFFIC, PARKING OF VEHICLES, STOCKPILING OF MATERIALS AND STORAGE OF EQUIPMENT OVER LEACHING AREA PROHIBITED AT ALL
- 2) REMOVE ANY TOPSOIL, SUBSOIL OR ANY OTHER UNSUITABLE MATERIAL BELOW THE INVERT FOR A DISTANCE OF 5 FEET AROUND THE PROPOSED FACILITY, FILL MATERIAL MUST MEET THE SPECIFICATIONS OF 310 CMR 15.255(3) OF TITLE V. (SEE THIS SHEET)
- 3) ALL CONSTRUCTION IS TO CONFORM TO THE REQUIREMENTS OF THE MASSACHU-SETTS STATE ENVIRONMENTAL CODE, TITLE V, AND THE DEDHAM BOARD OF HEALTH REGULATIONS.
- 4) SANITARY TEES ARE TO BE INSTALLED AT BOTH THE INLET AND OUTLET OF THE SEPTIC TANK. BUILT-IN TEES ARE NOT ALLOWED.
- 5) EXCAVATION IS TO BE DRY AND SCARIFIED.
- 6) FILL SHALL BE STOCKPILED AT EDGE OF FOUNDATION AND PUSHED OR CAST INWARD OVER EXCAVATED AREA.
- 7) FILL SHALL NOT BE PLACED DURING RAIN OR SNOW STORMS.
- 8) DEWATERING IS REQUIRED IF FILL IS TO BE PLACED BELOW GROUNDWATER.
- 9) BUILDING SEWER IS TO HAVE TIGHT JOINTS & LAID ON A FIRM COMPACTED
- 10) ALL SYSTEM COMPONENTS SHALL BE MARKED WITH MAGNETIC MARKING TAPE. 11) AN INSPECTION PORT, WHICH CONSISTS OF A PERFORATED PIPE PLACED VERTICALLY DOWN INTO THE STONE TO THE NATURALLY OCCURRING SOIL OR SAND BELOW THE STONE, IS REQUIRED. SCREW TYPE CAP ACCESSIBLE TO WITHIN 3" OF PROPOSED GRADE.
- 12) BENCHMARK TO BE SET WITHIN 50' OF SEPTIC SYSTEM AT THE TIME OF CONSTRUCTION IN AN AREA NOT SUBJECT TO DISLOCATION.

SEPTIC SYSTEM PLAN LOT 2 DETAILS 123 WESTFIELD ST. DEDHAM, MASSACHUSETTS

FEBRUARY 5, 2020 SCALE: NTS

Norwood

Norwood Engineering Company, Inc. Consulting Engineers, Land Surveyors 1410 ROUTE ONE, NORWOOD, MA 02062 TEL. (781)762-0143 FAX (781)762-8595



10296-01

